



RIG 10 INVENTORY

DRAWWORKS:

*Ideco H-44C Single Drum Drawworks, 700 HP, Lebus Grooved for 1-1/8" Drilling Line, Koomey Crown-O-Matic p/b (2) Detroit 8V-71N Diesel Engines with (2) Allison Mod. CLBT-5860 Transmissions, Foster Makeup & Breakout Catheads

MAST & SUBSTRUCTURE:

*Ideco 108'H Telescoping Mast, 268,000# Static Hook Load, (2) 3-Stage Hydraulic Raising Rams, Racking Board, Ladder, Guylines, Fluorescent Lights, 3-1/2" ID Standpipe w/Oteco 4" & 2" Gate Valves, Mud Pressure Gauge, Ingersoll Rand 5UH Air Hoist, Ideco Crown Block Assembly
*Ideco 11'H x 7'W x 14'L Substructure 275,000# Setback Capacity, Right Angle Rotary Drive, 10'W x 55" L Ramp

MUD PUMPS:

*(2) PZ-7 500 HP Triplex Mud Pumps, Independently p/b Cat D-379 Engines

ROTARY EQUIPMENT:

*Ideco 20-1/2" Rotary Table w/54-1/4" Centers, Varco Split Master Bushing
*Ideco TL-200, 200 Ton, Swivel
*(1) 40'L x 4-1/4" Square Kelly
*(1) Foster Model 77 Kelly Spinner
*(1) Varco 4KRUS Kelly Drive Bushing, Square Drive
*(1) TIW Upper Kelly Cock
*(2) TIW Lower Kelly Cock

TRAVELING EQUIPMENT:

*Ideco UTB-160 Shorty 160 Ton Block
*Ideco UTB-160 Shorty Ton Hook
*Set Elevator Links

HANDLING TOOLS:

*(1) Set Woolley Type B Manual Rotary Tongs
*(1) Set Varco 4-1/2" Drill Pipe Slips w/4" Dies
*(1) Set Varco Drill Collar Slips, 6" OD
*(1) Woolley 4" Drill Pipe Elevators
*(1) Baash Ross 7" Elevators

BOPs:

*Cameron Type "U" 11" x 5000 PSI Double Ram Preventer
*(2) 1-set of 3-1/2" Rams
*(2) 1-set of 4-1/2" Rams
*(2) 1-Set Blind Rams
*(2) 1-Set Casing 7" Rams
*(1) Drilling Spool, 12"H x 11" x 3000 PSI w/2 Outlets
*Cameron 3 Station Closing Unit (1) 80 Gallon Spherical Accumulator Bottle, (1) Hydraulic Pump, (1) Pneumatic Pump
*(2) Station Remote Closing Unit
*Cameron 3000 PSI BOP Choke Manifold w/(1) 4-Way Cross (2) 2-1/16" x 3M & (2) 3" x 3M Gate Valves

BOPs (continued):

*(1) 2-1/16" Adjustable Choke
*(2) 3-1/8" x 5000 PSI Gate Valves on Kill Side
*(1) 2-1/16" x 5000 PSI Gate Valve
*(1) 2-1/16" x 5000 PSI Flanged Check Valve

RIG HOUSES:

*(1) Onsite Champion 34' Fifth Wheel Trailer (for rig managers)

MUD SYSTEMS:

*(1) 500 Bbl. Mud Tank, (4) Compartments w/(1) Mission Centrifugal Desilter Pump & (1) Mission Centrifugal Mud Mixing, Stirrer Pump
*(1) Vortex, Orbital Motion Shale Shaker
*(1) Varco 8 Cone Desilter
*(1) 400 Bbl. Fresh Water Tank

AUXILIARY EQUIPMENT:

*Rig Tarps for Floor & Sub & Derrick Board
*(2) Electric Heaters
*Numerous Crossover Subs
*(2) Each Bit Subs, 4-1/2" IF Box Up by 4-1/2" Regular Box Down, Bored for Baker Float
*(2) Each Bit Subs, 3-1/2" IF Box Up by 3-1/2" Regular Box Down, Bored for Baker Float
*(1) 3683 Gallon Fuel Tank
*(1) Utility House with Accumulator Unit
*(1) 380 KW Gen Set w/14 Liter 60 Series Detroit Engine
*(1) Cat 275 KW Generator Set, Cat 3406 Diesel Engine
*(1) Drillers Instrumentation Box with Martin Decker Weight Indicator, Type Clipper, Atlas Pump Pressure Gauge, Tong Line Pull Gauge, Rotary Torque Gauge
*(1) Drillers Instrumentation Console with Control Valves for M/B Tongs, Mud Pumps, Transmission Shifters, Rotary Table and Drawworks Hoisting Clutch
*Bottom Change House with 12 Each Lockers, Benches, and Insulated with (1) Electric Heater and Parts Room
*(1) Top Dog House with Drillers Knowledge Box, Tool Box, Electrical Outlets, Satellite Automatic Driller Type Apollo and (1) Each Electric Heater (8'W x 18'L)
*Lot of Rig Lights and Wiring
*Web Wilson Type C Safety Clamps 5-1/2" to 6"
*(4) Pipe Racks, 36"H x 28'L
*(5) Stairways
*V-Door Ramp
*(8) 20# Fire Extinguishers Type ABC
*(1) Lot Documentation to include rig books, equipment, passports, and drawings